DEPARTMENT OF THE ARMY Omaha District, Corps of Engineers 106 South 15th Street Omaha, Nebraska 68102-1618

:NOTICE: Failure to acknowledge: Solicitation No. DACW45 03 B 0010

:all amendments may cause rejec- :

:tion of the bid. See FAR : Date of Issue: 31 Mar 2003

:52.214-3 of <u>Section 00100</u> : New Date of Opening: 02 May 2003

Amendment No. 0001 18 April 2003

SUBJECT: Amendment No. 0001 to Specifications and Drawings for Construction of Rearing Ponds and Hatchery Complex, Fort Peck Fish Hatchery, Fort Peck, MT.

Solicitation No. DACW45 03 B 0010.

TO: Prospective Bidders and Others Concerned

- 1. The specifications and drawings for subject project are hereby modified as follows (revise all specification indices, attachment lists, and drawing indices accordingly).
 - a. Specifications. (Descriptive Changes.)
- (1) Page 00010-1, delete date and time of bid opening shown and substitute "02 May 2003" at "2:00 pm".
 - (2) Section 00800 Page 3, add the following new paragraph:
- "1.1.3 Earthwork Drawing Files.

For informational purposes, the Contractor is provided the .dgn and .dtm files (Mircostation) to assist in earthwork quantity take-offs. These files are on the amendment CD and are accessed by going to your CD drive through Explorer.

ftpeck3.dtm	Microstation Digital Terrain Model of
	existing ground surface
fp22surv.dgn	Survey File
fp22site.dgn	Building Area Site Plan File
fp22pond.dgn	Pond Area Site Plan File
fp22cont.dgn	3D New Finish Grade Contours File "

- (3) Section 16261A Page 9, paragraph 3.1.1, line 1 delete "as necessary" and substitute "as determined by the VFD and motor supplier".
 - (4) Section 01355 Page 9, add the following new paragraph:
- "1.11 ENVIRONMENTAL COORDINATION, PERMITS, NOTICES, REVIEWS AND/OR APPROVALS

The Contractor shall be responsible for contacting the appropriate Federal, State, Regional, and local environmental agencies to identify all required environmental permits (construction and operating), notices, reviews, and approvals required for the project. Once the requirements are identified,

the Contractor shall be responsible for coordinating the requirements with the Contracting Officer in regard to implementation. The Contractor shall ensure that all coordination, permits, notices, reviews and/or approvals are completed and submitted with each applicable phase of the design. Prior to construction starting for any phase, the Contractor shall assure that all permits and/or approvals are received and copies are submitted to the Contracting Officer. The Contractor shall be responsible for any contract delays resulting from failure to obtain environmental permits, notices, reviews and/or approvals when required.

- 1.11.1 Applications, Supporting Documents, and Fees
 The Contractor shall obtain and complete all environmental permit
 applications and notices including any documents required for a modification
 for an existing permit held by the Facility. The Contractor is responsible
 for preparing all supporting documents, including but not limited to
 engineering reports, emission surveys, diagrams, pollutant load calculations,
 etc. If, in lieu of permits, the governing agency requires review and
 approval of the design, the Contractor shall submit and obtain approval of
 the design and associated documents. The Contractor shall be responsible for
 all fees associated with the permits, applications, reviews, approvals, and
 notices.
- 1.11.2 Environmental Permits, Notices, Reviews, and/or Approvals

The following is a listing of permits, notices, reviews, and/or approvals which **may be** required for this project. This listing and requirements are not to be considered all-inclusive by the Contractor, but is provided as information that may be used in successfully accomplishing the environmental compliances.

a. If construction activities results in disturbance of 1 acre of land or more (sites that may be smaller than 1 acre but are part of common plan of development are considered to be over 1 acre), coverage under the State of Montana Department of Environmental Quality, web site http://www.deq.state.mt.us/wqinfo/MPDES/PermitTypes.asp, Authorization to Discharge Under the Surface Water Discharge System Permit #MTR100000 is required. The Contractor shall be responsible for implementing the terms and requirements of the permit and shall be considered the "permittee". The Contractor shall complete and submit a Notice of Intent (NOI) and the Notice of Termination (NOT) in accordance with Permit #MTR100000 and shall be considered the "Facility Operator". The Contractor shall not begin construction until an authorization letter from the State granting coverage for the storm water discharges is received. The Contractor shall be responsible for posting a copy of the NOI and the authorization letter at the construction site in a prominent place for public viewing. The Contractor shall prepare and implement a Storm Water Pollution Prevention Plan, inspections, and reporting in accordance with the #MTR100000. Any temporary or permanent erosion and sedimentation control measures shown on the drawings shall be incorporated into the Contractor's Storm Water Pollution Prevention Plan. The Contractor shall be responsible for assuring that their SWPPP is in accordance with best management practices. The Contractor shall retain copies of the storm water pollution prevention plan and all reports in accordance with the permit. All submissions to the State shall be by certified mail. The Contractor shall include copies of all submittals to the State of Montana, plans, and reports in the Appendix to the Environmental Protection Plan.

- b. Prior to initiating work on connection of the hatchery complex, to the Fort Peck sewer system, the Contractor shall contact and pay the necessary fees (\$150.00) to the town of Fort Peck, attention Charles Carlson for a Sewer Service Initiation/Tapping Fee.
- c. Prior to initiating work on connection of the hatchery complex the Contract shall contact the Fort Peck Rural County Water District, attention Bobbi Skyberg, the Contractor shall submit a \$500 tapping application fee and a \$1500.00 tapping fee. See the attached form, to be completed and submitted with the \$500 initial application fee. "
- b. <u>Specifications (New and/or Revised and Reissued)</u>. Delete and substitute or add specification pages as noted below. The substituted pages are revised and reissued with this amendment.

Pages Deleted Pages Substituted or Added

--- Attachment to Section 01355:
Application for Introduction of Water Services

- Attachments to Section 01569:

Notice of Intent
Storm Water Pollution Prevention Plan
Notice of Termination

- c. <u>Drawings (Not Reissued).</u> The following drawing sheet is revised as indicated below with latest revision date of 18 April 2003. This drawing is not reissued with this amendment.
- (1) Sheet fp22u405, delete the notes and substitute the following new notes:
- "1. Existing pumps, motors and associated hardware, including lifting chain, cables, pump mounts, safety chain hooks, pipe guides, pipe connections, control/electrical connections, and trash rack shall be relocated from the existing lift station.
- 2. An electrical disconnect/junction box shall be installed adjacent to the new lift station to allow pump wiring to be disconnected at the wetwell.
- 3. Lighting shall be provided inside the new lift station wetwell, as it currently exists in the existing lift station.
- 4. The discharge piping (forcemain) from the new lift station shall be connected to the existing forcemain prior to the existing valve box/generator building. All piping penetrations into the existing lift station shall be transferred and replicated at the new lift station. This shall include the overflow line and all gravity connections into the existing lift station.
- 5. The hatch opening size shall be as in the existing lift station.
- 6. The existing pumps and guide rail system shall be re-located to the new wetwell.
- 7. Wet well is a Class I, Division I Group C&D Area. Provide a seal-off on all electrical conduit entering the wet well area."

d. <u>Drawings (Reissued).</u> The following drawing sheets are revised with latest revision date of 18 April 2003, and reissued with this amendment:

```
FP22P207.CAL
             P2.07
                          REMOVAL PLAN - AREA 7
FP22P208.CAL P2.08
                         REMOVAL PLAN - AREA 8
FP22C201.CAL C2.01
                          STORM DRAIN PROFILES
FP22A102.CAL A1.02
                          FLOOR PLAN- AREA B
FP22A104.CAL A1.04
                          FLOOR PLAN- AREA D
                         FLOOR PLAN- AREA H & J
FP22A108.CAL A1.08
                         UPPER LEVEL - AREA A
FP22A130.CAL A1.30
FP22A131.CAL A1.31
                         UPPER LEVEL - AREA B
FP22A401.CAL A4.01
                         EXTERIOR ELEVATIONS
FP22A402.CAL A4.02
FP22A403.CAL A4.03
FP22A404.CAL A4.04
FP22A501.CAL A5.01
                         EAST ELEVATION
                         WEST ELEVATION
                         SOUTH ELEVATION
BUILDING SECTIONS
BUILDING SECTIONS
FP22A502.CAL A5.02
FP22A503.CAL A5.03
                         BUILDING SECTIONS
FP22A510.CAL A5.10
                         WALL SECTIONS
FP22A511.CAL A5.11
                         WALL SECTIONS
FP22A512.CAL A5.12
                         WALL SECTIONS
FP22A513.CAL A5.13
                          WALL SECTIONS
FP22A514.CAL A5.14
                          WALL SECTIONS
FP22A515.CAL A5.15
                         WALL SECTIONS
FP22A530.CAL A5.30
                         STAIR SECTIONS
                         STAIR DETAILS
FP22A532.CAL A5.32
FP22A604.CAL A6.04
FP22A702.CAL A7.02
                         LOUVER SCHEDULE
                         DOOR DETAILS
                        ROOF DETAILS
FP22A801.CAL A8.01
FP22A802.CAL A8.02
                         ROOF DETAILS
FP22A803.CAL A8.03
FP22A804.CAL A8.04
                         ROOF DETAILS
FP22A905.CAL A9.05
                         CEILING DETAILS
FP22AC1.CAL
              AC.01
                          COMPOSITE FLOOR PLAN
FP22AC2.CAL
              AC.02
                          COMPOSITE UPPER LEVEL FLOOR PLAN
FP22S001.CAL S0.01
FP22S100.CAL S1.00
                          STRUCTURAL NOTES AND SCHEDULES
                          COMPOSITE FOUNDATION PLAN
FP22S101.CAL S1.01
                         FOUNDATION PLAN - AREA A
FP22S102.CAL S1.02
                         FOUNDATION PLAN - AREA B
FP22S103.CAL S1.03
                         FOUNDATION PLAN - AREA C
FP22S104.CAL S1.04
                         FOUNDATION PLAN - AREA D
FP22S105.CAL S1.05
FP22S106.CAL S1.06
                         FOUNDATION PLAN - AREA E
                        FOUNDATION PLAN - AREA F
FOUNDATION PLAN - AREA G
FP22S107.CAL S1.07
FP22S200.CAL S2.00
                         COMPOSITE ROOF FRAMING PLAN
FP22S201.CAL S2.01
                         ROOF FRAMING PLAN - AREA A
FP22S202.CAL S2.02
                         ROOF FRAMING PLAN - AREA B
                         ROOF FRAMING PLAN - AREA C
FP22S203.CAL
              S2.03
                          ROOF FRAMING PLAN - AREA D
FP22S204.CAL
              S2.04
                          ROOF FRAMING PLAN - AREA E
FP22S205.CAL
              S2.05
                         ROOF FRAMING PLAN - AREA F
FP22S206.CAL S2.06
FP22S207.CAL S2.07
                         ROOF FRAMING PLAN - AREA G
FP22S208.CAL S2.08
                         MEZZANINE FRAMING PLANS - AREAS H & J
FP22S209.CAL S2.09
                         ROOF FRAMING PLAN - AREA K
FP22S210.CAL S2.10
                         ROOF FRAMING PLAN - AREA L
FP22S402.CAL S4.02
                         FOUNDATION SECTIONS AND DETAILS
```

```
FP22S403.CAL S4.03 FOUNDATION SECTIONS AND DETAILS
FP22S404.CAL S4.04 FOUNDATION SECTIONS AND DETAILS
FP22S405.CAL S4.05 FOUNDATION SECTIONS AND DETAILS
FP22S406.CAL S4.06 FOUNDATION SECTIONS AND DETAILS
FP22S408.CAL S4.08 FOUNDATION SECTIONS AND DETAILS
FP22S501.CAL S5.01 FRAMING ELEVATIONS - LINES 1, 2, & 2.1
FP22S502.CAL S5.02 FRAMING ELEVATIONS - LINES 2.2, 2.3 2.4 & 2.5
FP22S503.CAL S5.03 FRAMING ELEVATIONS - LINES 3, 4, 4.1, 4.2, 4.4, 6,
                                                                                            6.1 & 7
FP22S504.CAL S5.04 FRAMING ELEVATIONS - LINES 4.5, 5, 7.2, 8, 8.5 & 9
FP22S505.CAL S5.05 FRAMING ELEVATIONS - LINES 10, 10.1, A, B & B.2
FP22S506.CAL S5.06 FRAMING ELEVATIONS - LINES B.5 & C
FP22S507.CAL S5.07 FRAMING ELEVATIONS - LINES C.1, C.2, C.4 & D
FP22S508.CAL S5.08 FRAMING ELEVATIONS - LINES E, F, F.1 & H
FP22S509.CAL S5.09 FRAMING ELEVATIONS - LINES H.1, J & K
FP22S510.CAL S5.10 FRAMING ELEVATIONS - LINES H.1, J & K
FP22S601.CAL S6.01 FRAMING SECTIONS AND DETAILS
FP22S602.CAL S6.02 FRAMING SECTIONS AND DETAILS
FP22S603.CAL S6.03 FRAMING SECTIONS AND DETAILS
FP22S604.CAL S6.04 FRAMING SECTIONS AND DETAILS
 FP22S604.CAL
                                                 S6.04
                                                                                   FRAMING SECTIONS AND DETAILS
                                                 S6.05
                                                                                   FRAMING SECTIONS AND DETAILS
 FP22S605.CAL
FP22S605.CAL S6.05 FRAMING SECTIONS AND DETAILS
FP22S606.CAL S6.06 FRAMING SECTIONS AND DETAILS
FP22S607.CAL S6.07 FRAMING SECTIONS AND DETAILS
FP22S608.CAL S6.08 FRAMING SECTIONS AND DETAILS
FP22S609.CAL S6.09 FRAMING SECTIONS AND DETAILS
FP22S804.CAL S8.04 REARING PONDS AND BROOD PONDS - CHIMNEYS
FP22S805.CAL S8.05 REARING PONDS AND BROOD PONDS - KETTLES
FP22M702.CAL M7.02 PROCESS PIPING PLAN - AREA 2
FP22M802.CAL M8.02 PROCESS PIPING - ENLARGED MECHANICAL ROOM -
                                                                                               1ST FLOOR
 FP22M804.CAL M8.04
                                                                           PROCESS PIPING - PIPING PROFILE AND
                                                                                        MECHANICAL ROOM ELEVATION
 FP22M805.CAL M8.05
                                                                                    PROCESS PIPING - RACEWAY AND SUPPLY TRENCH DETAILS
 FP22E501.CAL
                                                  E5.01
                                                                                     POWER ONE-LINE DIAGRAM - SCHEDULES AND DETAILS
```

e. $\underline{\text{Drawings (New)}}$. The following new drawing sheets dated 18 April 2003 are hereby added to the contract drawings and are issued with this amendment:

```
FP22S408.CAL S4.08 FOUNDATION SECTIONS AND DETAILS FP22S610.CAL S6.10 FRAMING SECTIONS AND DETAILS
```

- 2. This amendment is a part of the bidding papers and its receipt shall be acknowledged on the Standard Form 1442. All other conditions and requirements of the specifications remain unchanged. If the bids have been mailed prior to receiving this amendment, you will notify the office where bids are opened, in the specified manner, immediately of its receipt and of any changes in your bid occasioned thereby.
- a. <u>Hand-Carried Bids</u> shall be delivered to the U.S. Army Corps of Engineers, Omaha District, Contracting Division (Room 301), 106 South 15th Street, Omaha, Nebraska 68102-1618.
- b. $\underline{\text{Mailed Bids}}$ shall be addressed as noted in Item 8 on Page 00010-1 of Standard Form 1442.
 - 3. Bids will be received until 2:00 p.m., local time at place of bid

opening, 02 May 2003.

Attachments:

Spec Pages listed in $1.\underline{b}$ above Dwgs. listed in $1.\underline{d}$ and $1.\underline{e}$ above

U.S. Army Engineer District, Omaha Corps of Engineers 106 South 15th Street Omaha, Nebraska 68102-1618

18 Apr 2003 MFS/4411

APPLICATION FOR INTRODUCTION OF WATER SERVICE TO A PREVIOUSLY UNSERVED TRACT OR PARCEL OF LAND

(Submit Originals in Duplicate)

2. · 3. 4.	Application fee is submitted herewith. \$500.00
4.	
	Legal description of tract or parcel of land:
5.	The (DEDICATED) (PROPOSED) attached plat shows the tract or parcel of land to be erved.
6.	Whereas the above described tract or parcel of land has not previously participated in the onstruction of any water main or appurtenances. Therefore, said tract is assessed the tandard water main construction fee in the amount of \$\infty\$ \text{\text{O}} which is a bubmitted herewith.
7.	f commercial, or three or more dwelling units (existing) (proposed) complete the ollowing:
	Total number of dwelling units
	Total population to be served
	Average demand gpm.
	Maximum demand gpm.
	Water service size
	Water meter size
8.	less than three dwelling units:
	Water service size
	Water meter size

		•		
Fort Peck Rural County Water	District		•	
P.O. Box 228				
Fort Peck, MT, 59223	•			
G. H. was				
Gentlemen:				
An introduction of water ser previously unserved property public water main, but has ne to the water supply system appurtenances according to the of the Fort Peck Rural County the event that the area to be so County Water District, we agree to include the above describe the maintenance of the water property, and hereby agree to	Said property fronts and a ver been assessed for the control of th	abuts a right-cost of constraint the water olutions, Police vern municipate limits of ty Commission ance district of the fronting that as shall be	of-way contains of water an exter service line sies, and Ordina al water service the Fort Peck Foners are authoriceated by then he above described.	ing a sion and ances and arcade. Ir Rura rized n for ribed
We further agree to a bonded necessary permits and tap fees	d licensed plumber or pub s prior to installation of the	lic works cor desired water	ntractor securin r service.	g al
We further agree to a bonded necessary permits and tap fees Record Owner's Signa	s prior to installation of the	lic works cor desired water	ntractor securin r service. Date	g al
necessary permits and tap fees	s prior to installation of the	lic works cor desired water	r service.	g al
necessary permits and tap fees Record Owner's Signa	s prior to installation of the	lic works cordesired water	Date	g al
Record Owner's Signa Record Owner's Signa Record Owner's Signa Record Owner's Signa If a Corporate Owner, by	s prior to installation of the	desired water	Date Date	

TABLED:_____

NOI NUMBER	DEO Will Assign):

MONTANA DEPARTMENT OF ENVIRONMENTAL QUALITY WATER PROTECTION BUREAU/STORM WATER PROGRAM PO Box 200901 / Helena, MT / 59620-0901

NOTICE OF INTENT (NOI) FORM

GENERAL PERMIT FOR STORM WATER DISCHARGE ASSOCIATED WITH CONSTRUCTION ACTIVITY

<u>IMPORTANT</u>: Before completing this form, all parties need to read the General Permit. For coverage to be valid upon receipt by the Department, all required items on the form must be completed. Responses must be self-explanatory and must not refer exclusively to attached maps, plans, or documents. The Storm Water Pollution Prevention Plan (SWPPP) and appropriate fees must accompany the NOI Form. Do not submit these items separately. Mail this NOI Form to the DEQ address above. The 2002-2006 General Permit, 2002 Fee Schedule, and related forms are available from the Storm Water Program at (406) 444-3080 or http://www.deq.state.mt.us/wginfo/MPDES/StormwaterConstruction.asp.

I. OPERATOR INFORMATION

OPERATOR #1

List each party participating in the construction activity—from initiation of construction through final stabilization—that will be an operator as defined in Part V.T.8. of the General Permit. (Examples: primary contractor, project owner, site/land owners, consultants, or other contractors, such as the "final stabilization" contractor). For each operator, briefly describe responsibilities (what, when, where) for ensuring compliance with General Permit requirements.

Name: U.S. Army Corps of Engineers Phone: (402) 221-3826 Mailing Address: 106 South 15th Street Zip Code: |68102-1618 State: NE Contact Person: Harold Dingman Phone (if different from above): (406) 526-3411 Operator #1 Responsibilities Operator #1 has operational control over the construction plans and specifications, including the ability to make modifications to the plans and specifications. **OPERATOR #2** Name: Phone: Zip Code: Mailing Address: State: Contact Person: Phone (if different from above): Operator #2 Responsibilities:

Name:			Phone:		
Mailing Address:		State:		Zip Code:	
Contact Person:	Phone (if d	lifferent from abo	ve):		
Operator #3 Responsibilities:					
NDICATE WHICH OPERATOR IS RESPO	ONSIBLE FOR:				
A) Achieving "final stabilization" of the		erator 2 O	perator 3		
B) Submitting the "Notice of Terminati	•		•		Operator 3
C) Payment of any subsequent annual f		•	•		-
Construction Activity Inform			•		.,
A) Construction Activity Name: Rearing	`		•)		
B) Construction Activity Address (or lo					
Ft Peck, MT	scatton if no address).				
T C GOK, WIT					
C) Construction Activity County: Valle	э Э				
D) MDT Project Number/Designation					
E) Construction Activity Latitude and I		General Permit)			
· ·	e: 48 deg 01' 10"	General Fermity.			
F) Number and Names of Receiving Su	urface Waters (See Part I C 2 e	of General Permit	Descri	ne clearly	The number
named or perennial receiving surface	`			•	
USGS topographic map showing pr		•			
All discharges from the project will flow to the		•			
outside of the rearing and brood ponds will	discharge into the Missouri River at	t three locations via	culverts a	and storm o	Irain. Dischar
from the rearing and brood ponds will be di discharge to the Missouri River and shall be			econdary	settling po	onds prior to
C) Type of Construction Activity Fac (
G) Type of Construction Activity Fee (H) Indicate the Application and First Y					

NOI NUMBER (DEQ Will Assign):

	NOI NUMBER (DEQ Will Assign):
I) Brief Description of Purpose and Nature of Construction Act	tivity:
The purpose of the project is to rear fish for release to the wild. The psecondary settling ponds, hatchery building, parking areas and roads.	roject includes: 40 brood stock and rearing ponds, primary and
J) Estimated Construction Activity Start Date: 1 June 03	
K) Estimated Construction Activity Completion Date: 1 June (0.5
L) Estimated Final Stabilization Completion Date: 1 June 05	
M) Estimate of Total Acreage of Construction-related Disturba	nag. 94
N) Has a Storm Water Pollution Prevention Plan been develop	
with this Notice of Intent? YES NO	The decording to 1 art 1 v of the deficial 1 crimit and submitted
CERTIFICATION	
"I certify under penalty of law that this document and all attach	nments were prepared under my direction or supervision in
accordance with a system designed to assure that qualified personal transfer of the system designed to assure that qualified personal transfer of the system designed to assure that qualified personal transfer of the system designed to assure that qualified personal transfer of the system designed to assure that qualified personal transfer of the system designed to assure that qualified personal transfer of the system designed to assure that qualified personal transfer of the system designed to assure that qualified personal transfer of the system designed to assure that qualified personal transfer of the system designed to assure that qualified personal transfer of the system designed to assure that qualified personal transfer of the system designed to assure that qualified personal transfer of the system designed to assure that qualified personal transfer of the system designed to assure that qualified personal transfer of the system designed to assure that qualified personal transfer of the system designed transfer of the system designe	
submitted. Based on my inquiry of the person or persons who	
gathering the information, the information submitted is, to the	best of my knowledge and belief, true, accurate, and
complete. I am aware that there are significant penalties for sul	omitting false information, including the possibility of fine of
imprisonment for knowing violations."	
Kurt F. Ubbelohde	COL EN COMMAND'G
Print Name of Operator #1 or Authorized Representative	Title
Signature of Operator # 1 (Name must match that above)	Date
Print Name of Operator #2 or Authorized Representative	Title
Signature of Operator #2 (Name must match that above)	Date
Print Name of Operator #3 or Authorized Representative	Title
Signature of Operator #3 (Name must match that above)	Date

MONTANA DEPARTMENT OF ENVIRONMENTAL QUALITY

WATER PROTECTION BUREAU/STORM WATER PROGRAM PO Box 200901 / Helena, MT / 59620-0901

NOTICE OF TERMINATION (NOT) FORM GENERAL PERMIT FOR STORM WATER DISCHARGE

ASSOCIATED WITH CONSTRUCTION ACTIVITY

IMPORTANT: Before completing this form, all parties need to read the General Permit and the Notice of Intent (NOI) Form that was submitted. For termination to be valid upon receipt by the Department, all required items on the form must be completed. Responses must be self-explanatory and must not refer exclusively to attached maps, plans, or documents. The submittal of this NOT Form does not relieve the permittees of liability for annual fees that accrued during the period of active General Permit coverage. Only one NOT Form may be submitted for a respective NOI. Mail this NOT Form to the DEQ address above. The 2002-2006 General Permit, 2002 Fee Schedule, and related forms are available from the Storm Water Program at (406) 444-3080 or http://www.deq.state.mt.us/wqinfo/MPDES/StormwaterConstruction.asp.

I. INDICATE NOI NUMBER: MTR10	(Note: This number is indicated on the Confirmation Letter sent to
	operators upon receipt by the Department of a complete NOI package)

II. OPERATOR INFORMATION

List each operator that was provided on the Notice of Intent originally submitted. The Notice of Intent Form specified which operator is responsible for submitting the Notice of Termination. This operator should complete and sign this NOT Form, unless Reason For Termination "B" is checked below. Parties permitted under the 1997-2002 General Permit must list the "contractor" as Operator #1, and the "owner" as Operator #2 as stated on the Application form originally submitted.

OPERATOR #1 Name: U.S. Army Corps of Engineers Phone: (402) 221-3826 Mailing Address: 106 South 15th Street Zip Code: 68102-1618 State: NE Contact Person: Harold Dingman Phone (if different from above): (406) 526-3411 **OPERATOR #2** Phone: Name: Mailing Address: State: Zip Code: Contact Person: Phone (if different from above):

Name:		Ph	one:
Mailing Address:		State:	Zip Code:
Contact Person:	Phone (if dif	ferent from above):	
CONSTRUCTION ACTIVITY INFOR			
A) Construction Activity Name: Rea	ring Ponds and Hatchery Complex		
B) Construction Activity Address (or	location if no address):		
Ft Peck, MT			
C) Construction Activity County: Val	ley		
D) Construction Activity Latitude and	l Longitude (See Part I.C.2.d. of Go	eneral Permit):	
Longitude: 106 deg 27' 30" Latitude:	48 deg 01' 10"		
E) Brief Description of Purpose and N	Nature of Construction Activity:		
The purpose of the project is to rear fi primary and secondary settling ponds	· -		od stock and rearing ponds

IV. REASON FOR TERMINATION

Indicate the reason this Notice of Termination is being submitted by checking one of the following:

- A) Site has achieved "final stabilization" as defined in Part V.T.6. of the General Permit; or
- B) Operators identified on original NOI Form have changed.

IMPORTANT: The General Permit, and the corresponding NOI Form, are designed to provide coverage for all parties designated an "operator" at any time during the construction activity. The NOI Form and the SWPPP delineate who has what responsibilities, and during what portion of the project. Each NOI Form for a construction activity is designed to have only one corresponding NOT Form submitted for it, by the single operator identified as having this responsibility on the NOI Form. Reason for Termination "B" is not to be checked, and this NOT Form is not to be submitted, when a particular "operator" identified on the NOI Form is no longer active based on their identified responsibilities on the NOI Form. Reason for Termination "B" is only to be checked when an owner, contractor, etc. has been replaced (new owner - property sold, new contractor - contractor fired, etc.) based on operators identified on the original NOI Form. In this case, a new NOI Form will need to be submitted with all valid operators listed for the remainder of the construction project.

above, by the date of my signature below
efined in Part V.T.6. of the General Permit.
epared under my direction or supervision in
y gather and evaluate the information
stem, or those persons directly responsible for
owledge and belief, true, accurate, and
information, including the possibility of fine or
Title
Date

MONTANA DEPARTMENT OF ENVIRONMENTAL QUALITY WATER PROTECTION BUREAU/STORM WATER PROGRAM PO Box 200901 / Helena, MT / 59620-0901

STORM WATER POLLUTION PREVENTION PLAN (SWPPP) FORM GENERAL PERMIT FOR STORM WATER DISCHARGE ASSOCIATED WITH CONSTRUCTION ACTIVITY

IMPORTANT (READ THIS BEFORE COMPLETING FORM): Before completing this form all parties need to read the General Permit, particularly Part IV on SWPPPs. This SWPPP Form is intended to assist operators in developing a SWPPP which complies with Part IV. of the General Permit. The SWPPP is a document which is developed to direct and assist operators in identifying sources of potential pollutants at the construction activity site, and Best Management Practices (BMPs) to be used to help ensure such pollutants do not impact receiving surface waters through storm water runoff. It is the operator's responsibility to ensure all required items in the General Permit are adequately addressed, and that the SWPPP is developed, implemented, and maintained. Additional narrative information may need to supplement this SWPPP Form in order to meet these requirements. A copy of the SWPPP must be maintained at the construction activity site as required in Part III.C. of the General Permit. Items I through III on this SWPPP Form must state information exactly the same as that indicated on the NOI Form. Attach additional pages as necessary with the item number on this form indicated. For coverage under the General Permit to be valid upon the submittal of a NOI Package, this package must include a complete NOI Form, SWPPP, and fee. Do not submit these items separately. Mail the NOI Package to the DEO address above. The 2002-2006 General Permit, 2002 Fee Schedule, and related forms are available from the Storm Water Program at (406) 444-3080 or http://www.deq.state.mt.us/wqinfo/MPDES/StormwaterConstruction.asp.

NOI	NUMBER	(DEQ v	will assign	when this form	(NOI Packag	e) is submitted): MTR1()		

I. **OPERATOR INFORMATION**

List each party participating in the construction activity—from initiation of construction through final stabilization that will be an operator as defined in Part V.T.8, of the General Permit, (Examples: primary contractor, project owner, site/land owners, consultants, or other contractors, such as the "final stabilization" contractor). For each operator, briefly describe responsibilities (what, when, where) for ensuring compliance with General Permit requirements.

OPERATOR #1

Name: U.S. Army Corps of Engineers	Phone: (402) 221-3826
Mailing Address: 106 South 15th Street	State: NE Zip Code: 68102-1618
Contact Person: Harold Dingman	Phone (if different from above): (406) 526-3411
Operator #1 Responsibilities:	
Operator #1 has operational control over the construction plans and the plans and specifications	specifications, including the ability to make modifications to

OPERATOR #2			
Name:		Phone:	
Mailing Address:		State:	Zip Code:
Contact Person:	F	Phone (if different fro	om above):
Operator #1 Responsibilities:			
OPERATOR #3			
		DI DI	
Name:		Phone:	
Mailing Address:		State:	Zip Code:
Contact Person:	F	Phone (if different from	om above):
Operator #1 Responsibilities:			
INDICATE WHICH OPERATOR IS RESPON	ISIBLE FOR:		
A) Achieving "final stabilization" of the si	ite: Operator #2		
B) Submitting the "Notice of Termination		only): Operator #2	
CONSTRUCTION ACTIVITY INFORMATIO	`	•	
A) Construction Activity Name: Rearing		orripiex	
B) Construction Activity Address (or local	ition if no address):		
Ft Peck, MT			
C) Construction Activity County: Valley			
D) MDT Project Number/Designation (if	applicable):		
E) Construction Activity Latitude and Lor	ngitude (Refer to Part I.	C.2.d. of General Pe	rmit):
Longitude: 106 deg 27' 30" Latitude	: 48 deg 01' 10"		
F) Estimated Construction Activity Start I	Date: 1 June 03		
G) Estimated Construction Activity Comp			
o, Loumand Constitution Activity Comp	Jacaba Date. 1 dans do		

H) Estimated Final Stabilization Completion Date: 1 June 05

IV. GENERAL SWPPP REQUIREMENTS

Name:	Affiliation:	MT License No.:
B) Brief Description of Pu	rpose and Nature of Construction Activity:	
	to rear fish for release to the wild. The project inc s, hatchery building, parking areas and roads.	ludes: 40 brood stock and rearing ponds, primary
C) Proposed Implementation	on Schedule for Major Activities (indicate where where the second	hich operators are responsible for each
Operator #2 is responsible fo	r all activities listed below.	
Construct contractor stages Existing topsoil from area Install temporary silt fence Construct new building, u Install inlet protection. Complete fine grading of Topsoil and seed disturb Remove silt fencing and	is to be graded shall be stripped and stockpiled. ing along downhill perimeter of the site where indicitilities, pavements.	cated and begin rough grading of the site.
	of the Site (and all other sites if a phased dev	velopment project):
99		
E) Estimate of Total Area	of the Site Expected to Undergo Disturbance	Related to Construction Activity:

G) Are sand & gravel excavation, other borrow areas, and/or crushing operations associated with project?
Yes No v
Are temporary asphalt batch plant operations associated with this project?
Yes No v
If yes, be sure to include the requested information about these areas on the site map, or a similar separate map, as stated in Part IV.G.1.c. of the General Permit.
H) Describe the character and erodibility of sediment and other earth material to be disturbed at the project site,
including cut/fill material to be used:
The top 14 feet (approximately) of existing soils at the site consist of lean clay (CL) and fat clay (CH) which has a low erosion potential. Soils below 14 feet consist of sand (SP) which has a high erosion potential. Existing soils shall be used as fill material.
I) Estimate of Runoff Coefficient and Increase In Impervious Area (refer to Part IV.G.1.e. of the General Permit - only applies if total construction-related disturbance is 5 acres or more):
The runoff coefficient for the site after construction completion will be approximately 0.6. The amount of impervious area will increase 56 acres. 53 acres of the impervious area consists of HDPE-lined rearing and brood ponds which will be drained once per year.
J) Indicate Names of Receiving Waters and Describe the Size, Type, and Location of each Point Source Discharge or
Outfall (refer to Part IV.G.1.f. of General Permit):
All discharges from the project will flow to the Missouri River which is approximately 150 feet from the site. Discharges from the areas south and west of the rearing ponds will be collected in a ditch and directed to the river through a 48-inch diameter culvert. Discharges from the paved and turfed areas around the new hatchery building will flow into a 24-inch storm drain pipe and on to the river. Discharges from the new wetland area and existing areas south of the hatchery complex will flow through a ditch along the east side of the complex. Discharges form the rearing and brood ponds will be directed through underground piping to the primary and secondary settling ponds prior to discharge to the Missouri River and will be covered under a separate permit.

K) Describe Storm Water Discharges From Support Activities (refer to Part IV.G.1.g. of General Permit):					

V. SWPPP BEST MANAGEMENT PRACTICES (BMPs) AND STORM WATER MANAGEMENT CONTROLS

A) Describe Applicable Local Erosion and Sediment Control Requirements:		
There are no local erosion and sediment control requirements.		
B) Describe in detail, temporary BMPs and storm water management controls which will be used for erosion and/or sediment control during construction-related earthwork activities. Indicate the location of these measures on the site map required above, or a similar separate map, as much as practicable. Include a schedule for implementation for each of these measures. Attached details and specifications may be used to supplement this description. Refer to Parts IV.G.2.a.,b.,c. of the General Permit. Examples of temporary measures could include but are not limited to: slope roughening; vegetative buffer strips; silt fences; straw bale dikes; erosion control blankets/mats; temporary drain diversions; minimizing clearing; temporary sediment basins/traps; mulching; temporary seeding; brush barriers; up-slope runoff diversions/controls; inlet/outlet protection; disturbance area runoff diversions/controls; waterway protection; and, ditch runoff flow dispersers (e.g. level spreaders)/flow inhibitors.		
Temporary stone construction entrance(s) shall be constructed at all vehicle entrances/exits to the project site prior to beginning land disturbance activities. Temporary silt fencing shall be installed along the downhill side of the project site where indicated prior to beginning land disturbance activities uphill from the fence. Silt fencing shall be removed only after the disturbed area uphill of the fencing has been stabilized. Any sediment deposits remaining in place after the silt fence is no longer required shall be dressed to conform with the existing grade, prepared and seeded. Temporary inlet projection shall be installed around inlets indicated immediately after construction and backfilling of drainage structure. Inlet protection shall be removed when the inlet drainage area has been stabilized. Erosion control blankets shall be installed on slopes and in ditches where indicated.		

measures to achieve final stabilization (as defined in Part V.T.6. of the General Permit). Indicate the location of these measures on the site map required above, or a similar separate map, as much as practicable. Attached details and specifications may be used to supplement this description. Refer to Parts IV.G.2.a.,b. of the General Permit. Examples of permanent measures could include but are not limited to: permanent seeding; check dams; retaining walls; drain inlet protection; rock outlet protection; drainage swales; sediment basin & traps; earth dikes; manmade erosion control structures; grassed waterways; sod stabilization; infiltration trenches or basins; subsurface drains; level spreader; terraced slopes; tree or shrub planting; pipe slope drains; vegetative buffer strips; detention ponds; and, containment ponds.
All areas disturbed by construction and not otherwise surfaced shall be topsoiled and seeded.
Outfall of culverts and storm drains will be lined with riprap to prevent scour.
D) Describe what products or wastes may be stored or utilized at the construction activity site, indicate on the site map as required above, and indicate what BMPs will be used to minimize potential pollutants from these materials
coming into contact with storm water runoff. Examples of products or wastes could include but is not limited to: fuels; concrete; masonry blocks; solvents; detergents; steel; roofing shingles; fertilizers; paints; tar; pesticides; lumber; other petroleum-based materials; other hazardous materials (including wastes); solid waste; and, concrete truck wastewater disposal.

C) Describe in detail, permanent and structural BMPs and storm water management controls which will be used for erosion and/or sediment control during and after construction-related earthwork activities. These would include

roads (examples include a graveled access entrance and exit drives and parking areas, and a tire wash pad at exit drive):
Temporary stone construction entrance(s) shall be constructed at all vehicle entrances/exits to the project site prior to beginning land disturbance activities. Any mud, dirt or rock tracked from the site on to Highway 117 shall be removed daily.
F) When trucking saturated soils from the site, either tight leak-proof trucks must be used or loads must be required to drain until drippage has been reduced to less than 1 gallon per hour before leaving the site. Will saturated soils be trucked from the site? Yes No No
G) Describe man-made and natural measures to control pollutants in storm water discharges after construction operations have been completed. Refer to Part IV.K. of the General Permit. Examples include: vegetative waterways and natural landscape; infiltration trenches or basins; storm water detention structures; wet ponds or man-made wetlands; and, storm water containment structures.
All areas disturbed by construction and not otherwise surfaced shall be topsoiled and seeded. New ditches and swales with vegetative lining shall be constructed at non-erodible slopes. Outfall of culverts and storm drains will be lined with riprap to prevent scour.

E) Describe any measures that will be used to prevent vehicle tracking of sediment from the construction site onto

H) BMPs must minimize or prevent "significant sediment" (as defined in Part V.T.13. of this General Permit) from leaving the construction site. If "significant sediment" results from the failure of erosion or sediment control measures, the operator(s) shall evaluate the effectiveness of such measures or other BMPs and incorporate improvements to minimize the potential for "significant sediment". Additionally, if "significant sediment" results from the failure of erosion or sediment control measures, the material must be cleaned up and placed back on the site or disposed of in an acceptable manner. The material must not be washed into the storm sewer(s), drainageway(s), or receiving surface waters. There may be obligations for the operator(s) to obtain other permits or permissions to clean up the "significant sediment."

VI. CERTIFICATION

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine or imprisonment for knowing violations."

Print Name of Operator #1 or Authorized Representative	Title
Signature of Operator # 1 (Name must match that above)	Date
Print Name of Operator #2 or Authorized Representative	Title
Signature of Operator #2 (Name must match that above)	Date
Print Name of Operator #3 or Authorized Representative	Title
Signature of Operator #3 (Name must match that above)	Date